



What, When and Why?

- In the late 1980's, the SMSCG was built to mitigate for upstream diversion of both federal and state water projects.
- Guiding Conceptual Model:
 - Reduced outflow increases salinity.
 - -Increased salinity reduces waterfowl food plant abundance and diversity.
- SMSCG was built to control salinity in the marsh and meet regulatory and contractual standards.


Concord Naval Weapons Station




SMSCG Components



SMSCG Significance Timeline of Events




Salinity Standard Compliance Locations Both regulatory and contractual




D1641 STANDARDS

FOR DELTA / MARSH REGIONS




Suisun Marsh Salinity Control Gate Configurations


June → September



October ⇒ May (when needed to meet standards)








Salinity Gradient

Operational Triggers:

- Closes on flood tide when velocity <= 0.1 fps
- Open on ebb tide when the head difference between u/s and d/s water levels >= 0.3 ft


SUISUN MARSH SALINITY CONTROL GATE FACILITY



EBB TIDE (Draining) = Gates Open




SUISUN MARSH SALINITY CONTROL GATE FACILITY




FLOOD TIDE (Filling) = Gates Closed



Tidal Time Scale Flows



Salinity Response to SMSCG Operation





SMSCG CHALLENGES

- Fisheries Issues/Concerns
- Safety issues/concerns with NOAA open boat lock requirement
- Aging of facility
- Unexpected constraints (i.e. Owl nesting)

Initial Facilities

- Required under the Plan of Protection for the Suisun Marsh
- •Roaring River Distribution System, Morrow Island
- Distribution System, and Goodyear Slough Outfall
- All initial facilities, except, GSO, were built in the early 1980's to provide lower salinity water to private and DFG managed wetlands.





RRDS Background

- Operational since 1980
- ~8 mi long
- Serves water to ~5000 Acres (private)
 ~3000 Acres (DFG)
- Intake pond on east side is about 40 acres
- Eight 60" diameter motorized slide gates culverts to divert water into pond equipped with fish screens and flap gates on the pond side
- Total of 40 turnout and drain structures
- Flood up first two weeks in October
- DFG land flood up in August (typically)

MIDS and GSO Background


MIDS:

- Operational since 1980.
- Three 48" culverts at intake to divert GYS water into MIDS.
- Drainage water from MIDS to Grizzly Bay via
 M-line and C-line outfalls, with ditch length about
 1.6 miles and 0.8 miles, respectively.
- MIDS provide water to four managed wetlands(~1400 acres).

GSO:

- Operational since 1980. 69' wide by 0.5 miles.
- Four 48" culverts with one-way flap gates on bay side allowing drainage to bay and close on flood to keep saltier bay water into GYS

Additional Resources



- http://www.water.ca.gov/suisun/
- Kate Le (<u>kle@water.ca.gov</u>), 916.375.9751, Suisun Marsh Program, DWR